

West Oakland Bay Saltmarsh Restoration Project ADVERTISEMENT FOR BID

Notice is hereby given that sealed proposals for the West Oakland Bay Saltmarsh Restoration project, near the city of Shelton, Mason County, WA, will be received at the offices of the SPSSEG, 6700 Martin Way E, Suite 112, Olympia, WA 98516 or via email at caseya@spsseg.org until **4:00 pm, Friday, May 29th, 2026**. Proposals received after the time fixed for opening will not be considered. Electronic proposals will be in a PDF format and including scanned copies of the original signed non-collusion certificate. Original signed copies must be produced prior to award of Contract.

This contract provides for the construction of the West Oakland Bay Saltmarsh Restoration project in Mason County. This project includes intertidal work, is permitted for work from the land and water (barge), and will require two construction seasons to complete (In-water work window July 16th-February 15th). The project is funded through a mix of state, federal, and Tribal dollars. The project includes the following elements:

- Demolition of sheet pile and wooden bulkheads, piling, concrete deck and asphalt paving.
- Procure and place lobe fill material, organics amendments, and lobe crest cobble on the south and west lobes, as well as grading of marsh channels.
- Procure and place lobe fill material, organics amendments, and lobe crest cobble on the north lobe, as well as grading of blind and marsh channels, and fill to support stormwater outfall extensions.
- Construct temporary and final stormwater outfall pipe extensions within north lobe area.
- Create access to west lobe through berm on the east side of SPI property and repair upon completion. Access south lobe through SPI property. Access not to interfere with mill operations, sites to be kept clean, repair all damage to site/infrastructure to pre-construction conditions or better.
- Establishment of staging area on SYC property (north lobe), maintain access for marina and yacht club, and reduce impacts to yacht club members and recreational marina users.
- Manage stormwater and material staging using BMPs and work below the high tide line completed only when the work area is not inundated.
- Complete required construction submittals.
- Coordinate with SPSSEG project managers and appointed representatives to facilitate construction oversight activities for the work.

Plans, specifications, permits, and other pertinent information can be obtained from SPSSEG upon request. Please contact Casey Allen, project manager, at

caseya@spsseg.org or 360.764.9132 to obtain copies of the bid package. The estimated cost of this contract is between \$5,000,000 and \$6,000,000. This is a Prevailing Wage project.

There will be a NON-mandatory pre-bid meeting on **Thursday, May 14th from 11:00am to 1:00pm**. The pre-bid meeting will entail a walking tour of the project site including multiple access routes, staging, sequencing and monitoring, demolition, material, and other project specifics. Please RSVP to Casey Allen, Project Manager, at caseya@spsseg.org if you plan to attend the pre-bid meeting.